

# RICHARD L. ROUDEBUSH VA MEDICAL CENTER | INDIANAPOLIS, IN



Front view of Richard L. Roudebush VA Medical Center



4th & 5th Floor, 29,500 Total SF Occupied Hospital



October 2008 – September 2009



\$500,000



MDM Construction Supply



Selective Interior Demolition



Asbestos & Lead Abatement



Infection Control



Mold Remediation



Zero OSHA Recordable Incidents

LVI conducted asbestos abatement and selective interior demolition of 9,500 square feet on the 4th floor and 20,000 square feet on the 5th floor of Indianapolis' fully-occupied Richard L. Roudebush VA Medical Center.

This was a highly sensitive project as the rest of the hospital remained occupied by patients, health professionals and hospital staff. Asbestos-containing materials abated included over 5,500 linear feet of pipe insulation; 20,000 square feet of contaminated plaster ceilings; 20,000 square feet of floor tile and mastic; and approximately 100 square feet of transite paneling. In addition to removing asbestos containing materials, LVI completely demolished the interior of the C-Wing on the fifth floor.

In addition to working in an area occupied by hospital patients below, LVI worked directly with the VA Medical Center's Infection Control Coordinator to organize our work methods to satisfy the infection control requirements set forth by the Department of Veterans Affairs.

The work was completed on-time and on-budget with zero OSHA recordables.

**Project Managed By** LVI Environmental Services Inc., a subsidiary of LVI Services Inc. | **Client Contact** Mike Close, MDM, (815) 222-6134, mclose@mdmconstructionsupply.com