

EAA A-1 FLOW EQUALIZATION BASIN (FEB)

| | |
|-----------------|--|
| CLIENT | South Florida Water Management District (SFWMD) |
| LOCATION | Palm Beach Co, FL |
| VALUE | \$ 60 M |
| DATE | Design: July 2013 - July 2013 Construction: July 2013 - Ongoing |
| SAFFTY | Zero OSHA Recordables |




Design Engineering Services and Engineering During Construction Services

NorthStar provided design engineering services for the Everglades Agricultural Area (EAA) A-1 Flow Equalization Basin (FEB) from conceptual through Corrected Final / Ready to Advertise design, and engineering during construction (EDC) services. The 15,000 acre EAA A-1 FEB will temporarily detain up to 60,000 ac ft of peak stormwater runoff flows for later controlled release. The concept and implementation of a flow equalization basin is a “first of its kind” project for SFWMD.

The key components of the NorthStar design include:

- 15,000 acre FEB with a 60,000 ac-ft attenuation capacity at an average depth of 4 ft
- 13 miles of perimeter levees (11 ft tall with 14 ft crest), 6.7 miles of flow conveyance levees (8 ft tall)
- ¾ mile of canal extensions; 2,700 linear ft collection and conveyance canal
- two multi-bay roller-gated spillway structures
- one 3-barrel slide gate culvert structure, 600 linear ft 3 barrel bypass box culvert
- one single barrel seepage collection culvert with two inlet structures
- 10 single barrel culverts with solar powered slide gates (first full-scale implementation for SFWMD)
- demolition & disposal of 60 miles of roadways, 3.1M cy of muck, and two agricultural pump stations
- 5 boat/access ramps, four 6,000 to 11,000 sf parking areas



NorthStar work activities are highlighted below.

- **Data review** - Review of reports, studies, models, and databases pertaining to the site, local hydrology and hydraulics, and operation of connecting conveyance systems in order to optimize the design.
- **Geotechnical investigation** - Characterization of stratigraphy, soil types, gradation (to evaluate suitability for embankment materials), consolidation, percolation rate, hydraulic conductivity, and groundwater levels.
- **Land surveying** - Surveys of topography, ROW, and boundary for modeling and design purposes.
- **Hydrologic & hydraulic modeling** - Modeling included use of TuFLOW (2-D flow modeling), HEC-RAS (conveyance structures), FEMA (wave setup), and MODFLOW (seepage).
- **Civil design** - Engineering design of 13 miles of perimeter levees with maintenance roads, 6.7 miles of flow conveyance levees, and appurtenant structures. Levee design included dam breach analysis and modeling.
- **Structural design** - Engineering design of reinforced concrete water control structures, including cost-saving construction options for cast-in-place concrete using HDPE and other alternative materials.
- **Electrical design** - Electrical, instrumentation, monitoring and control, SCADA, and telemetry design for water control gate structures; and monitoring instrumentation within the FEB.
- **Engineering during construction** - Observe construction, oversee RFI responses, review contractor submittals, attend progress meetings, and sign and seal as-built drawings as Engineer of Record.



NorthStar refined design parameters, configurations, and other options at every opportunity to optimize estimated costs and materials. Our design team identified \$2M in design optimizations/cost reductions, and our opinion of probable construction cost (OPCC) was within 7% of the actual construction bid of \$60M.

